

History of original corner establishment:

Corner originally established in 1881, by Eugene P. McCornack, under "General Land Office Contract" No. 398, Surveyor General's Notes State:
 Set Basalt stone 20x14x8 ins, 15 ins in the ground for cor to Secs. 19, 24, 25 and 30, marked with 4 notches on N and 2 notches on S Edges.
 from which

DIAGRAM

T7S
 R37E R38E
 1819

 1830
 1984
 PLS 2065

A Pine 20 ins. diam. bears N45E 58 lks. dist. marked T7S R38E S19 BT
 A Fir 24 ins diam bears S30E 60 lks. dist marked T7S R38E S30 BT
 A Pine 48 ins diam bears S50W 45 lks dist. marked T7S R38E S25 BT
 A Pine 30 ins diam bears N40W (can't read) marked T7S R38E S24 BT

Description of corner evidence found:

Found an old mound of stone with a 24"x12"x8" stone, with no marks apparently visible, lying downhill alongside mound. This is a granite stone and the marks have decomposed. There is a hole in the center of the stone mound where the above described stone was set.
 From Which (from center of stone mound)

A Pine, 48" dia., live in good condition, with scribing visible, bears S50W, 32.0 ft.
 A burned pine snag with scribing visible, bears N40E, 36.7 ft.
 A Pine 20" dia., live in good condition, with scribing reads S R37E S24 BT bears N40W., 30.2 ft.
 Root hole with remains of fir bears approx. record to SE bearing tree.
 Accepted said center of stone mound as the Sec. Cor. Position.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2-1/2" aluminum pipe with 2-1/2" aluminum cap stamped as shown on the DIAGRAM, set 14" in the ground set original stone alongside pipe & raised a mound of stone and earth around the pipe.

From which

A Fir 14" dia. bears S38 17'E., 90.64 ft. scribed T7S R38E S30 BT
 A Tamarack 6" dia. bears N41 15'E., 30.2 ft. scribed T7S R38E S19 BT

Nailed a brass washer stamped PLS 848, on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree.
 Painted a 6" red band at breast ht. around each tree.
 (Douglas M. Ferguson, PLS 848 scribed trees)

Set steel posts with warning and boundary signs North 4 ft. & South 3 ft. from cor.

Painted 6" red band around, and nailed bearing tree & warning signs to all original bearing trees.

Corner set Sept. 13, 1984
 Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

J. David Brinton

OREGON
 DECEMBER 2, 1983
 J. DAVID BRINTON
 2065

★ GPO—798-275

FILED 2-15-85
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-38-49