

History of original corner establishment:

Corner originally established in 1881, by Eugene P. McCornack, under "General Land Office Contract"

No. 398, Surveyor General's Notes State:

(Abridged Description) Set Post 4 ft long 4 ins square 24 ins in the ground, for cor., with std. markings, from which: A Black Pine 18" diam.

bears N20E, 27 lks. dist. A Black Pine 10 ins. diam.

bears S60E, 16 lks dist. A Black Pine 8 ins. diam. bears S20W 11 lks.

A Black Pine 16 ins. diam. bears N20W (can't read)

In 1974 the Bureau of Land Management Remonumented this corner. from existing physical evidence. See FIELD NOTES of the "REMONUMENTATION OF CERTAIN ORIGINAL CORNER POINT, TOWNSHIP 7 SOUTH, RANGE 38 EAST," as executed by Lester E.

Fischer, Cadastral Surveyor and James J. Carlson, Cadastral Surveyor, under special instructions dated May 3, 1957, approved May 6, 1957, under U.S. Survey Group No. 350.

Description of corner evidence found:

Found 3" brass cap monument set on 2-1/2" iron pipe, 4" above the ground, Stamped as shown on the DIAGRAM. The remains of the original post with scribing visible & 2" iron pipe, alongside brass cap monument.

Found remains of original bearing trees, as follows:

A root hole, bears S64-1/2E., 10.6 ft. with a down lodgepole pine alongside, with scribing visible.

A decayed stump, bears N20W., 17.8 ft. dist., with down lodgepole pine alongside, with scribing visible.

Found bearing trees taken by the BLM in 1975, as follow.

A spruce, 12" diam. bears N27-3/4E., 38.3 ft. scribed T7S R38E S30 BT

A spruce, 12" diam. bears S62-1/2E., 20.1 ft. scribed T7S R38E S31 BT

Description of monument and accessories | established to perpetuate the original location of this corner:

Maintained Corner by setting steel posts with warning and boundary signs North & South 5 ft. from corner.

Maintained accessories by painting blazes and 6" red band, on and around all found original and BLM trees, and nailing warning and bearing tree signs to all trees as needed.

DIAGRAM

T7S1T7S

R37E1S30

1S31

1R38E

1975 BLM

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J. David Brinton

OREGON
DECEMBER 2, 1983
J. DAVID BRINTON
2065

Corner set Sept. 13, 1984
Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)