

History of original corner establishment:

Corner originally established in 1882, by William R. Gradon, under "General Land Office Contract" No. 445, Surveyor Generals Notes State: Set a granite stone 16x12x12 ins. 11 ins, in the ground for 1/4 sec. cor. marked 1/4 on W. face. from which

DIAGRAM

T7S R38E
S30
1/4-.-
S31
CS 1976

A fir 8 ins. diam. bear. N75E., 14 lks. dist. marked 1/4 S BT
A fir 20 ins. diam. bear S45W., 20 lks. dist. marked 1/4 S BT
In 1976, James D. Hanley found the original stone and the section 31 bearing tree stump and set a 2" iron pipe with 3" brass cap stamped as shown on the DIAGRAM, set 8" above the ground, in a mound of stone and earth.
From which, new bearing trees:
A fir 8" diam. bears N08E., 8.1 ft. dist. marked 1/4 S30 BT
A fir 10" diam. bears S41E., 35.3 ft. dist. marked 1/4 S31 BT

Description of corner evidence found:

Found 2" iron pipe with 3" brass cap monument, stamped as shown on the DIAGRAM, set with 8" above the ground.

Found bearing trees as taken by James D Hanley, in 1976.
A fir 9" diam. bears. N BE., 8.1 ft. with scribing visible.
A fir 11" diam. bears. S41E., 35.3 ft. with scribing visible.
both trees are live in good condition.

Description of monument and accessories | established to perpetuate the original location of this corner:

Maintained Corner by setting a steel post with warning sign West 1 ft. from corner,

Maintained Accessories as follows:

Nailed Bearing Tree Sign above blaze, and warning sign on back of each tree.
Painted a 6" red band at breast ht. around each tree.



Corner Maintained Sept. 15, 1984
Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)