

History of original corner establishment:

Corner originally established in 1881, by Eugene P. McCornack, under "General Land Office Contract" No. 398.

In 1978 the Bureau of Land Management Performed A Dependent Resurvey of A portion of the South Boundary of T.7S., R.38E., Under special instructions, dated March 13, 1978, approved March 28, 1978.

The Notes from that survey, as executed by Dale T. Bedell, cadastral surveyor, states:

(Abridged Notes) At proportionate distance; there is no remaining evidence of the original corner. Set standard monument, mkd. (see DIAGRAM) from which:
 A fir, 17 ins. diam., bears N45E., 40 lks. dist., mkd. T7S R38E S33 BT
 A fir, 13 ins. diam., bears S85E., 22 lks. dist., mkd. T8S R38E S4 BT
 A fir, 10 ins. diam., bears S27W., 24 lks. dist., mkd. T8S R38E S5 BT
 A fir, 8 ins. diam., bears N17-1/2W., 19 lks. dist., mkd. T7S R38E S32 BT

Description of corner evidence found:

Found 2-1/2" iron pipe with 3" brass cap monument stamped as shown on the DIAGRAM, set with 6" above the ground.

Found all the trees as taken by the BLM in 1978, live in good condition, at record measurement, with scribing visible.

Description of monument and accessories I established to perpetuate the original location of this corner:

Maintained Corner monument by setting a steel post with warning sign 1 ft. north from corner.

Maintained accessories as follows:

Nailed Bearing Tree Sign above blaze, and warning sign on back of each tree.
 Painted a 6" red band at breast ht. around each tree.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J. David Brinton

OREGON
DECEMBER 2, 1983
J. DAVID BRINTON
2065

Corner maintained Sept. 15, 1984
 Witnessed by Douglas M. Ferguson, PLS 848

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....

..... by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 2-15-85

BAKER COUNTY SURVEYOR

SURVEY NO. 7-38-62

8-38-

DIAGRAM

T7S R38E
 S321933

 S S1S 4
 T8S R38E
 1978