



Found, ~~original~~ 1/2" iron pin
 This determined not original. Disregard, it does not relate to the culture or other monumentation.

The original monument (iron rod) is lost.

Original monument at SW cor. Block "O" is lost.

250.0' to E.M.T. This point not set this survey.

Note: Only 2 of the original monuments in this part of Haines are now in place. The iron pin one of 5th St. on West line of Ruby Street is the correct distance from center line of UPRR M.T. The town was laid out parallel and at right angle to the railroad, and the railroad is therefore a part of the original monumentation.

The original monument at SE cor. of Block 7 is lost.

Found, the original iron pin monument 1/2" x 3/4" 8" deep in ground

MAP OF SURVEY
 IN BLOCK "M", HAINES TOWNSITE

For Methodist Church

June 13 & Sept. 26, 1978
 & Oct. 2, 1978

Scale 1" = 100' REGISTERED PROFESSIONAL LAND SURVEYOR

- o Found, monument as noted
- Set 5/8" rebar, Oct. 2, 1978

FILED Oct. 2, 1978
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-39-10

James D. Hanley
 OREGON
 SEPTEMBER 23, 1977
 JAMES D. HANLEY
 1206