



BASIS OF BEARING
 SOLAR OBSERVATION
 SEPT 1, 1978

- LEGEND
- FOUND MONUMENT OF RECORD
BRASS CAP MARKED C.S. 1975
 - SET 5/8" x 30" REBAR w/ CAP
MARKED AP&A AT BEGINNING POINT
 - SET 5/8" x 30" REBAR w/ CAP
MARKED AP&A AT APPROXIMATE
CORNERS. SET FOR ALIGNMENT.

A parcel of land in the NW $\frac{1}{4}$ Section 34, T7S R39E, W.M., Baker County, Oregon. Beginning at a 5/8" x 30" steel pin being S73° 04' 32" West, 5105.62 feet from the northeast corner of Section 34, T7S, R39E, W.M.

Thence S75° 34' 52" West, a distance of 100 feet more or less, to the easterly line of that property recorded on microfilm Deed No. 76-33-032 and 76-33-033, Baker County Oregon.

Thence N14° 25' 08" West, more or less, along the said easterly property line, a distance of 100 feet more or less, to the southerly right-of-way line of Baker County Road No. 690. Said right-of-way line being parallel to and at a right angle distance of 30 feet from the existing road centerline.

Thence N78° 32' 40" East, 100.13 feet more or less, along the county road right-of-way.

Thence S14° 25' 08" East, to the Beginning Point, a distance of 94.84 feet more or less.

Containing 0.22 acres more or less.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Barry B. Barbour

OREGON
 OCT. 17, 1975
 BARRY B. BARBOUR
 10511

PROPERTY SURVEY
 PORTION OF NW 1/4 SEC. 34, T7S, R39E, W.M.
 BAKER COUNTY, OREGON

FOR: CITY OF HAINES

SCALE:
 1" = 40'

DATE:
 1978

**Anderson
 Perry**
 & Associates, Inc.
 engineering • surveying • materials testing
 LA GRANDE & ENTERPRISE, OREGON

SHEET NO.
 1/1

FILED Jan. 9, 1979
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-39-12