



NARRATIVE

The purpose of this survey for Norville Marr was to mark on the ground the property described in Deeds 90-18-143 and 80-36-100. Record deed bearing and distances were held as controlling except where the bearing was described as being along a sectional subdivision line or parallel to a sectional subdivision line (as along the west boundary). Street locations shown are based on found monumentation on Fifth Street, U.P.R.R. Centerline and the original monument at the Northeast corner of Block 9, Haines Townsite.

REGISTERED PROFESSIONAL LAND SURVEYOR
James D. Hanley
 OREGON
 SEPTEMBER 23, 1977
 JAMES D. HANLEY
 1206

HANLEY ENGINEERING
 2043 MAIN STREET
 BAKER CITY, OREGON

MAP OF SURVEY
 IN THE N1/2 S1/2 SW1/4, SECTION 33
 T. 7S., R. 39E., W.M.

Surveyed June 1990
 Scale 1" = 100'

LEGEND

- FOUND MONUMENT AS NOTED
- SET 5/8" X 30" REBAR WITH YELLOW PLASTIC CAP MARKED "HANLEY ENGRG PLS 1206"
- [] RECORD BEARING/DISTANCE DEED 80-36-100
- () RECORD BEARING / DISTANCE DEED 90-18-143

SURVEY REFERENCES: 7-39-30, 7-39-31 AND 7-39-33

FILED JULY 2, 1990
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-39-39

(NORTH 994.20')
 [N. 0° 47' 22"E. 994.20']
 [SOUTH]
 East Line SW Quarter of Section

FENCE CORNER
 1/4 CORNER
 SECTION 33