

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T. 7 S., R. 40 E.

R - 17

RECOVERED BY	COORDINATE SYSTEM, ZONE, & UNIT	
Matthew Faulkner, Oregon PLS	United States/NAD83, Oregon North 3601, International foot	
GCDB ID	NORTHING	EASTING
500300	473806.02	8903923.16
LATITUDE	LONGITUDE	
N44°56'02.379"	W117°47'21.420"	

	S22	S23	
	S27	S26	

RECORD OF ORIGINAL CORNER AND SUBSEQUENT HISTORY:

The cor. of secs. 22, 23, 26 and 27, T. 7 S., R. 40 E., was originally established and described in the field notes of the survey of the subdivisional lines of T. 7 S., R. 40 E., Willamette Meridian, Oregon, executed by U.S. Deputy Surveyors David P. Thompson and Daniel Chaplin in 1864, under Contract Number 104.

Description: Set stone, 18x10x8 ins. For cor. to secs. 22, 23, 26 and 27.

DESCRIPTION OF CORNER EVIDENCE FOUND AND DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE THE LOCATION OF THIS CORNER:

Recovery Date: 9/23/2023

Description: The cor. of secs. 22, 23, 26 and 27, monumented with a basalt stone, 18x10x8 ins., lying loose on the ground, mkd. with 2 notches on an edge and 4 notches on an edge 90° to the 2-notch edge.

At the corner point

Set an aluminum post, 30 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, over a plastic-encased magnet, and in a collar of stone, 3 ft. diam., to the top of an aluminum cap as shown on this corner record.

from the aluminum post I add the following reference monuments

A rebar, 30 ins. long, 5/8 ins. diam., 24 ins. in the ground, bears S. 12°06'43" E., 100.05 ft. dist., with yellow plastic cap mkd. S&F LAND SERVICES.

A rebar, 30 ins. long, 5/8 ins. diam., 24 ins. in the ground, bears N. 47°20'37" W., 99.93 ft. dist., with yellow plastic cap mkd. S&F LAND SERVICES.

Basis of Bearings: Oregon North State Plane Coordinate System NAD83 2011 (Epoch 2010.0).
All bearings for reference monuments that I set are in reference to said Oregon North State Plane. Distances shown hereon are ground distances, International Feet.

Buried the original basalt alongside the aluminum post.

Corner is in the corner of barbed wire fences, from which barbed wire fences extend S. and W.

Corner is also located, W., 110 ft. dist., from a trail road, 15 lks. wide, bears S. 70° E. and N. 70° W.

Set a steel fence post, N. of the aluminum post, approximately 1 1/2 ft. dist.

FILED January 29, 2025
BAKER COUNTY SURVEYOR
SURVEY NO. 7-40-26

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Photo No.1 of the basalt stone,
mkd. with 2 notches on an edge.




Photo No. 2 of the basalt stone,
mkd. with 2 notches on an edge.



Photo No. 1 of the basalt stone,
mkd. with 4 notches on an edge.




Photo No. 2 of the basalt stone,
mkd. with 4 notches on an edge.



Photo of the aluminum monument
set in a collar of stone and in
the corner of barbed wire
fences.



Diagram of the aluminum cap
markings.



**BAKER COUNTY
SURVEYOR**

Date Received _____

January 29, 2025
Date Filed

By _____

File No. 7-40-26

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

OREGON

JUNE 08, 2009
MATTHEW J. FAULKNER
75618LS

RENEWS: 12/31/25