

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

E-25


**History of original corner establishment:**

W. B. Barr conducted the survey of Township 7 South, Range 43 East, W.M., August 29 to September 8, 1881, under GLO Contract No. 388, dated May 7, 1881.

The original notes of that survey relative to this corner state the following:

Set a stake 4 ft. long, 4 in. dia., 18 ins. into the ground for corner to sections 1x6x7x12. From which:

- A Fir, 18 ins. dia., bears S. 60° W., at 7 lks. dist.
- A Fir, 60 ins. dia., bears S. 20° E., at 5 lks. dist.
- A Fir, 18 ins. dia., bears N. 70° W., at 30 lks. dist.
- A Fir, 15 ins. dia., bears N. 76° E., at 6 lks. dist.



**Description of corner evidence found:**

Found a W. Fir, 34 ins. dia., bearing N. 81° W., at 19.8 ft. dist. mkd. healed over  
A down Fir, 20 ins. dia., bears S. 60° W., at 4.6 ft. dist. mkd. S12 the rest of the scribe is healed over.

**Description of monument and accessories established to perpetuate the original location of this corner:**

Set a 2 1/2" x 30" alum. pipe with a 2 1/2" alum. cap 24 ins. into the ground. The cap is marked as shown in the corner diagram. From the corner point:

- A W. Fir, 7 ins. dia., bears S. 24° W., at 22.6 ft. dist., mkd. T7S R42E S12 BT.
- A W. Fir, 13 ins. dia., bears S. 45° E., at 41.9 ft. dist., mkd. T7S R43E S7 BT.
- A W. Fir, 16 ins. dia., bears S. 80° E., at 77.2 ft. dist., mkd. T7S R43E S6 BT.

Set a steel fence post 4 ft. Southerly on line and attached a 54-2 and 54-9 USFS sign. Also set a steel fence post 4 ft. Easterly on line and attached a 54-2 USFS sign. Painted the face of the blaze and a 6 in. band around the bearing trees red. Attached I.D. washer and USFS 54-9 and 54-3 signs to bearing trees. Used 18 1/2° declination on a staff compass for readings to bearing trees. Used a steel tape to measure to a nail set in the side of the trees.

The corner was established from the original bearing trees.

This corner was remonumented to USFS specifications on Dec. 9, 1986, witnessed by Tom Fisk and Larry McBroom.

Office of.....County Surveyor..... County of..... Baker.....  
State of.....OR....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 9/24/86

BAKER COUNTY SURVEYOR

SURVEY NO. 7-42-184

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*James D. Hanley*  
OREGON  
SEPTEMBER 24, 1977  
JAMES D. HANLEY  
1206

★ GPO-788-276