

aerial photo projections and GPS data. A more thorough survey would be necessary to isolate which rocks would merit a more intense investigation.

The SE section corner was a post and most likely all evidence of that post is gone. It is also likely that farming was done in the area which would further eliminate any post evidence. There was a Cottonwood bearing tree and there is one small grove of 3 or 4 trees in the vicinity. I did not find any scribing or blaze evidence on any of the existing trees. Cottonwoods are fairly short lived trees and I expect the existing trees are progeny of the original BT. These trees can help isolate the area in which the corner should be found, but will be of limited use in determining the original corner position most likely.

This is being submitted to the Baker County Surveyor records as information only and not a certified record of survey. The intent is to help perpetuate the limited evidence found of the original GLO survey.

FILED DECEMBER 13, 2004
BAKER COUNTY SURVEYOR
SURVEY NO. 7-42-20