

RECORD OF LAND CORNER MONUMENTATION

NORTH 1/16 CORNER SECTIONS 23 & 24, T. 7 S., R. 42 E., W.M.

ORIGINALLY ESTABLISHED BY: CORNER NOT PREVIOUSLY ESTABLISHED

CONTRACT NUMBER: N/A

CONTRACT DATE: N/A

14	13	13	18
23	24	24	19
23	24	24	19
26	25	25	30

ORIGINAL DESCRIPTION: N/A

EVIDENCE FOUND: N/A

DESCRIPTION OF MONUMENTS AND ACCESSORIES SET AND METHODS USED:

At the corner point as determined by survey, I set a 5/8"x12" iron pin 6" into a drill hole in exposed bedrock, and attached a 3 3/4" brass cap. Built a 2 ft. diameter mound of stone around the monument to top of cap. Cap is marked as shown below.


From which, I SCRIBE A NEW BEARING TREE:

- ▶ A ponderosa pine 22" dbh bears N.18°W., 37.37 ft. marked N1/16 S23 in upper blaze and BT in lower blaze

Also from which, I SET A NEW REFERENCE POINT:

- ▶ A 5/8"x 9" iron pin, set 6" into a drill hole in exposed bedrock, bears S.44°56'E., 24.83 ft., with attached 2" aluminum cap marked RP 1 2024 PLS 69454

CORNER MONUMENT MARKED:



Painted a 6 inch red band around the new bearing tree, and also painted blazes red and attached USFS 54-3 and 54-9 signs. Used RTK GPS to measure the reference point and bearing to BT. Used a steel tape to measure distance to the BT, measuring to a 6" Mag Spike driven in the side-center-right at the root crown of the tree, with an attached 1 1/2" aluminum washer stamped PLS 69454. Bearings are geodetic, derived by GPS observation at the corner. Set aluminum guard posts North and East, with USFS signs 54-2 and 54-9 attached.

RESTORATION BY, STAMP AND DATE:

Work performed April 16, 2024 by:

Jason L. Hatfield, PLS

USDA FOREST SERVICE
NORTHEAST OREGON LAND ZONE
1550 Dewey Avenue, Suite A
Baker City, OR 97814
(541) 523-1283

FILED May 23, 2024
BAKER COUNTY SURVEYOR
SURVEY NO. 7-42-34

REGISTERED
PROFESSIONAL
LAND SURVEYOR


OREGON
NOVEMBER 30, 2007
JASON L. HATFIELD
#69454
EXPIRES: 6/30/2025