

RECORD OF LAND CORNER MONUMENTATION

SOUTHEAST CORNER SECTION 22, T. 7 S., R. 42 E., W.M.

ORIGINALLY ESTABLISHED BY: William B. Barr, U.S. Deputy Surveyor

CONTRACT NUMBER: 355

CONTRACT DATE: June 14, 1880

SUBSEQUENT SURVEYS: Narrative titled "Corner Search in Section 27, T7S, R42E By Leland Myers on November 27, 2004" filed December 13, 2004 as Survey No. 7-42-20

16	15			15	14
21	22			22	23
21	22			22	23
28	27			27	26

ORIGINAL DESCRIPTION:

Marked Basalt rock 18x16x6 for corner to Sections 22X23X26X27, Raised mound of rock as per instructions

MYERS' DESCRIPTION: Myers made a preliminary evaluation, but did not conduct a search for the marked stone. He states that he believes the old down fence running South "was or is very near the section line"

EVIDENCE FOUND: Found a 3 ft. diameter mound of earth and embedded stones at the intersection of old down fence remains running East, South, and West. I also found a bridge spike with flagging attached, set in the center of the mound. I searched for but did not find the original marked stone. The mound of stone is harmoniously related to other found corners in the area and is accepted as the best available evidence of the original section corner.

There is also a rock jack corner constructed in recent years, with fences running East, South, and West, which lies about 9 feet South and 3 feet West of the accepted corner. Mr. Myers' narrative makes no mention of the existence of this fence corner at the time of his field visit in 2004.


DESCRIPTION OF MONUMENTS AND ACCESSORIES SET AND METHODS USED:

At the corner point, I set a standard USFS 2½"x30" aluminum pipe with attached 3¼" aluminum cap 26" in the ground. Built a 3 ft. diameter mound of stone around the monument to top of cap. Cap is marked as shown below.

From which, I SET NEW REFERENCE POINTS:

- ▶ A 5/8"x 24" iron pin, bears N.44°56'E., 7.17 ft., with attached 2" aluminum cap marked RP 1 2024 PLS 69454
- ▶ A 5/8"x 24" iron pin, bears S.48°14'E., 8.62 ft., with attached 2" aluminum cap marked RP 2 2024 PLS 69454
- ▶ A 5/8"x 24" iron pin, bears S.44°20'W., 7.01 ft., with attached 2" aluminum cap marked RP 3 2024 PLS 69454
- ▶ A 5/8"x 24" iron pin, bears N.45°13'W., 10.60 ft., with attached 2" aluminum cap marked RP 4 2024 PLS 69454

CORNER MONUMENT
MARKED:



Placed a blue plastic-encased magnet at the base of the aluminum pipe. Used RTK GPS to measure reference points. Bearings are geodetic, derived by GPS observation at the corner. Set an aluminum guard post alongside, with 54-9 sign attached.

RESTORATION BY, STAMP AND DATE:

Work performed April 8, 2024 by:

Jason L. Hatfield, PLS

USDA FOREST SERVICE
NORTHEAST OREGON LAND ZONE
1550 Dewey Avenue, Suite A
Baker City, OR 97814
(541) 523-1283

FILED May 23, 2024
BAKER COUNTY SURVEYOR
SURVEY NO. 7-42-43

