

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by Gordon C. Smith, under instructions dated January 13, 1940, for mineral survey #867.

Set a 1"x36" galvanized iron pipe 28" in ground, marked "03-S1-E2-A4" "867" from which;

a pine 18" in diameter bears S 88° E 34.7 feet distance, marked "03-S1-E2-A4-867" "BT"

a tamarack 18" in diameter bears S 66° W 25.5 feet distance, marked "03-S1-E2-A4-867 BT"



Description of corner evidence found:
Found no evidence of original pipe.

Found tamarack 18" in diameter S 73° W 25.5 feet distance, with partly healed face, scribing visible. Alive and well.

Found ponderosa pine snag 22" in diameter S 88° E 34.7 feet distance, scribed "E2-04-S1-867BT"

Distances to original bearing trees are to the face.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2½"x30" aluminum pipe with ¾" aluminum cap 24" in ground in mound of stone. Cap marked;

Bearing trees


a ponderosa pine 11" in diameter bears N 08° W 26.7 feet distance, scribed "S1-E2-03-A4MS867" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

Compass declination 20° East

Note

I set a steel fence post with USFS Attention sign at corner, placed USFS 54-8 signs on all bearing trees, and painted red band on smooth bark at breast height on all bearing trees.

I hereby certify the above corner location was perpetuated as herein described on September 19, 1981.



Terry Butler, Witness

Frank Vaughn

Frank Vaughn, Witness

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet

OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)