

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established by Gordon C. Smith, under instructions dated January 13, 1940, for mineral survey #867.

Set a 1"x36" galvanized iron pipe 28" in ground marked "C1-C22-L3-G4-867" from which;

a fir 6" in diameter bears N 11° E 25.3 feet distance marked "C1-C22-L3-G4-867 BT"

a fir 6" in diameter bears S 11° W 36.0 feet distance marked "C1-C22-L3-G4-867 BT"



Description of corner evidence found:

Found no evidence of original pipe.

Found no evidence of southwest bearing tree.

Found fir 13" in diameter N 11° E 36.0 feet distance, opened face and found scribing "867"

Our retracement survey indicates that the distances to the bearing trees were reversed in the original notes.

All distances to bearing trees were to side and center.

Found 5/8" re-bar with yellow cap marked "HANLEY ENG" N 12° E 3.9 feet distance.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2 1/2"x30" aluminum pipe with 3 1/4" aluminum cap 26" in ground in mound of stone. Cap marked;

Bearing trees

a douglas fir 9" in diameter bears N 57° W 64.1 feet distance, scribed "C22-L3-C1-G4MS867" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

a ponderosa pine 8" in diameter bears S 75° E 58.1 feet distance, scribed "C22-L3-C1-G4MS867" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

Compass declination 20° East

Note


I set a steel fence post with USFS Attention sign at corner, placed USFS 54-8 signs on all bearing trees, and painted red band on smooth bark at breast height on all bearing trees.

I hereby certify the above corner location was perpetuated as herein described on September 27, 1981.

Terry Butler, Witness

Frank Vaughn

Frank Vaughn, Witness



REGISTERED PROFESSIONAL LAND SURVEYOR

Carl E. Sundet

OREGON JULY 14, 1978 CARL E. SUNDET 1664

Office of..... County of.....

State of..... I hereby certify that the within instrument was filed in this office

for record on the..... day of..... 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED Oct 27, 1981

☆ GPO—798-276

BAKER COUNTY SURVEYOR

SURVEY NO. 7-43-17