


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by W. Barr under contract # 388, dated May 7, 1881.
Set 4" x 4" stake 18" in ground from which;
a pine 48" in diameter bears N89°E - 49 lks
a tamarack 10" in diameter bears S37°W - 62 lks




Description of corner evidence found:

Found:
48" ponderosa pine - N89°E - 49 lks - (dead and down) scribed "1/4 S" - rotten
18" tamarack - S37°W - 62 lks - stump - scribed "T"
No evidence of original stake.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" x 30" aluminum pipe with 3 1/4" aluminum cap 24" in ground in mound of stone, marked:



Bearing trees:

12" douglas fir - N58°E - 57.1 ft. - scribed "1/4 S23" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.
7" ponderosa pine - S18 1/2°W - 49.9 ft. - scribed "1/4 S22" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

Compass declination 21 1/4° East

Note:

I set steel fence post at corner with USFS Attention sign, placed USFS bearing tree signs on all bearing trees and painted red band on smooth bark at breast height on all bearing trees.

I hereby certify the above corner location was perpetuated as herein described in August 1981,

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Terry Butler Terry Butler, Witness
Frank Vaughn Frank Vaughn, Witness

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by

(COUNTY OFFICIAL)

(DEPUTY)