


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by W. Barr, under contract # 388, dated May 7, 1881  
Set stake 4" x 4" 18" in ground from which;  
a fir 14" in diameter bears N13°E - 78 lks  
a pine 18" in diameter bears N8½°W - 83 lks  
a pine 20" in diameter bears S57½°E - 80 lks  
raised mound of stone



Description of corner evidence found:

Found:

- 41" douglas fir - N08½°E - 78 lks (live and grown over)
- 24" ponderosa pine stump - N12½°W - 83 lks - scribed "BT"

No evidence of original stake or stone mound.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2½" x 30" aluminum pipe with ¾" Aluminum cap 26" in ground, marked:

Bearing Trees:

- 13" ponderosa pine - N33°W - 47.5 ft. - scribed "T7S R43E S22" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.
- 16" ponderosa pine - S68½°W - 60.3 ft. - scribed "T7S R43E S27" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.
- 10" ponderosa pine - S35°E - 72.5 ft. - scribed "T7S R43E S26" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

Compass declination 21° East

Note:

I set steel fence posts at corner with USFS Attention Sign, placed USFS bearing tree signs on all bearing trees and painted red band on smooth bark at breast height on all bearing trees.

I hereby certify the above corner location was perpetuated as herein described in August 1981.

Terry Butler Terry Butler, Witness

Frank Vaughn Frank Vaughn, Witness



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Carl E. Sundet*

OREGON  
JULY 14, 1978  
CARL E. SUNDET  
1664

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL) (DEPUTY)