

SUNDET & ASSOCIATES

LAND SURVEYING

LAKEVIEW, OREGON 97630
PHONE 947-3293
P.O. Box 1228

December 2, 1981

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

Survey for: Wallowa-Whitman National Forest
P.O. Box 907
Baker, Oregon 97814

Location: Located in sections 24 & 25, T.7S.R.43E. and sections 19 & 30, T.7S.R.44E., Baker County, Oregon

Purpose: Monumentation of exterior corners and marking of the property line between private and Forest Service ownership.


Date: Survey completed November 1981

Procedure: Survey began with the search and evaluation of corners. Original evidence was found at all corner locations, however the survey bears out the fact that the bearing tree at C-3, E-3 has been moved by road construction, subsequently the corner was re-set by proportionate measurement. At corner C-22, L-3, C-1, G-4 it was determined through the survey that the distances to the bearing trees had been reversed, as was the case at NY-1, F-4. It should be noted here that the original surveyor was not consistent in measuring to the bearing trees. There were eight corners in this survey where the original pipe was still in position and at least one bearing tree could be verified, it was found that some bearing trees were measured side and center and some were measured to the face, Original bearings to bearing trees were usually unreliable.


A closed traverse was run around the nine mining claims tying in all exterior corners. The property line was marked with steel fence posts and F.S. property boundary signs. All corners surveyed thru were remonumented and perpetuated in accordance with the 1973 Manual.

Instruments used were a Mac I-H Electronic Distance Measuring Device, Jena one-second theodolite, 4 inch K & E staff compass and 100' steel tape.

Bearings are based on solar observation.



Carl E. Sundet



FILED Jan 5, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 7-43-45