

Corner Monumentation of
Mineral Survey No. 867
Located in portions of Sections 24 and
25, T. 7 S. R. 43 E., W.M. and Sections 19 and
30, T. 7 S. R. 44 E., W.M.
Baker County, Oregon
Forshey Cadastral

- ① NY 4
Fd: Unrecorded 4"x4" wood post .9' northwest of corner position.
Ref: 14" PPBT, with healed face, N 03 1/2° W -37.3' (N 07° W -37.3')
6" PPBT, dead and down, with weathered face, scribed "BT" N 17 1/2° W -33.3' (N 30° W -33.3')
Set: AP 24" in ground in mound of stone. Comp. decl. 20° East
Ref: 10" PPBT. S 12 1/2° E -23.7'
- ② NY 1-F 4
Fd: No evidence of original pipe.
Ref: 11" Tamarack, with healed face, S 80° E -19.0' (N 23° W -19.0')
6" Tamarack, dead and down, scribing unreadable, N 23° W -6.0' (S 80° E -6.0')
Set: AP 26" in ground in mound of stone. Comp. decl. 20° East
Ref: 7" PPBT. N 67 1/2° W -24.3'
- ③ F 1
Fd: 1" G.I.P. marked "F 1 867"
Ref: 18" Fir snag, scribed "867" in partly chopped open face, S 64 1/2° W -51.9' (S 60° W -51.9')
19" PPBT, with healed face, S 82° W -39.0' (S 77° W -39.0')
Set: AP 26" in ground in mound of stone. Buried original pipe alongside new monument. Comp. decl. 20° East
Ref: 11" PPBT. N 26° E -1.9'
- ④ 1/4 corner 24|19
Fd: BLM brass cap, 1974.
Ref: 30" Fir stump, with healed face, S 78° E -77 lks (S 78° E -77 lks)
32" PP. stump, scribed "1/4 S BT, West -5 lks (West -5 lks)
5" PPBT. N 74° E -39 lks
12" PPBT. N 84° W -46 lks
- ⑤ F 2-L 1
Fd: Unrecorded 1" pipe 1' northeast of corner position. No marks.
Ref: 18" WFBT, with healed face, S 15° E -28.8' (S 15° E -28.8')
Stump hole, N 21° E -28.0' (N 21° E -28.0')
Set: AP 26" in ground in mound of stone. Comp. decl. 20° East
Ref: 7" PPBT. S 66 1/2° E -28.4'
- ⑥ L 2-G 1-V 3
Fd: Unrecorded 1" pipe .7' northeast of corner position. No marks.
Ref: 11" PPBT, with healed face, S 49° E -23.7' (S 51° E -23.7')
PP. stump, no visible scribing, S 70° W -25.7' (S 67° W -25.7')
Set: AP 26" in ground in mound of stone. Comp. decl. 20° East
Ref: 8" PPBT. S 45° W -34.8'
- ⑦ G 2-V 2-S 4-E 3
Fd: 1" G.I.P. marked "G 2-S 4-E 3-V 2-867"
Ref: 8" Fir stump with log alongside scribed "V 2-E 3-S 4-G 2 867 BT" N 56° E -37.2' (N 51° E -36.5')
7" Fir, dead and down, N 41° E -41.2' (N 36° E -41.0')
Set: AP 24" in ground in mound of stone. Buried original pipe alongside new monument. Comp. decl. 20° East
Ref: 7" PPBT. S 47° W -20.9'
9" PPBT. S 37 1/2° E -33.2'

- ⑧ V 1-E 4-M 2
Fd: 1" G.I.P. bent over in edge of road.
Ref: 12" PPBT, scribed "M 2", N 60° E -16.6' (N 66° E -16.6')
No evidence of southwest BT. (S 36° W -25.5')
Set: AP 24" in ground in mound of stone. Buried original pipe alongside of new monument. Comp. decl. 20° East.
Ref: 14" PPBT. S 35° W -67.6'
- ⑨ M 3
Fd: 1" G.I.P. marked "M 3 867"; S 88° 45' 28" E -89.96'. Also found a 2 1/2" G.I.P. with a 2 1/2" brass cap, unmarked, .75' northeast of corner position.
Ref: 18" PPBT, scribed "M 3 867 BT", S 84° W -33.7' (S 81° W -33.7')
Decayed pine stump, no scribing, S 14° E -45.5' (S 15° E -45.5')
Set: AP 26" in ground in mound of stone. Buried original pipe alongside of new monument. Comp. decl. 20° East.
Ref: 10" PPBT. S 34° E -17.0'
9" PPBT. N 10° W -21.8'
- ⑩ M 4-P 2
Fd: 1" G.I.P. marked "P 2-M 4"
Ref: 21" Fir BT, with healed face, S 13° W -4.5' (S 15° W -4.5')
18" Fir BT, with healed face, S 37 1/2° E -13.3' (S 41° E -13.3')
Set: AP 26" in ground in mound of stone. Buried original pipe alongside of new monument. Comp. decl. 20° East.
- ⑪ E 1-M 1-P 1-A 1
Fd: 1" G.I.P. marked "M 1-A 1-P 1-E 1 867"
Ref: 13" PPBT, scribed "E 1-M 1-P 1-A 1 86", N 03 1/2° E -32.0' (N 17° W -17.0')
29" PPBT, scribed "E 1-M 1-P 1-A 1 867 BT", S 53° W -22.9' (S 34° W -36.4')
Set: AP 24" in ground in mound of stone. Buried original pipe and broken clear glass alongside of new monument. Comp. decl. 20° East
- ⑫ Section Corner 24, 25, 19, 30
Fd: BLM brass cap, 1974.
Ref: 24" PP. stump, no scribing, N 58 1/2° E -66 lks (N 58 1/2° E -66 lks)
33" PPBT, scribed "7 S S 30", S 32° E -30 lks (S 32° E -30 lks)
25" PP. stump, no scribing, N 25 1/2° W -99 lks (N 25 1/2° W -99 lks)
9" PPBT. N 54° E -28 lks
10" PPBT. S 63 1/2° E -23 lks
11" PPBT. S 67 1/2° W -82 lks
12" Fir BT. N 03° W -11.1 lks
- ⑬ S 1-E 2-O 3-A 4
Fd: No evidence of original pipe.
Ref: 18" Tamarack BT, with visible scribing, S 73° W -25.5' (S 66° W -25.5')
22" PP. snag, scribed "A 4-E 2-O 4-S 1 867 BT", S 88° E -34.7' (S 88° E -34.7')
Set: AP 24" in ground in mound of stone. Comp. decl. 20° East.
Ref: 11" PPBT. N 08° W -26.7'
- ⑭ E 1-S 2-O 2
Fd: 1" G.I.P. marked "O 2-E 1-S 2 867"
Ref: 14" Fir BT, with healed face, N 70° W -13.5' (N 72° W -13.5')
17" Fir BT, with healed face, N 53 1/2° E -17.1' (N 49° E -17.3')
Set: AP 24" in ground in mound of stone. Buried original pipe alongside of new monument. Comp. decl. 20° East.
- ⑮ E 2
Fd: 1" G.I.P. marked "E 2 867" in mound of stone.
Ref: 19" PPBT, scribed "E 2 867 BT", S 18 1/2° W -52.6' (S 14° W -52.0')
14" PP. snag, scribed "2 867 BT", N 43° W -149.3' (N 47° W -150.0')

- Set: AP 10" in ground in mound of stone. Buried original pipe alongside of new monument. Comp. decl. 20° East.
Ref: 6" PPBT. N 54° W -54.4'
- ⑯ C 3-E 3
Fd: No evidence of original pipe.
Ref: 18" Tamarack, dead and down, scribed "E 3-C 3 8", out of position. (N 54° W -28.2')
No evidence of Fir BT. (N 11° W -44.3')
Set: By single proportionate measurement, an AP 26" in ground in mound of stone. Comp. decl. 20° East.
Ref: 10" White Fir BT. N 18° E -55.6'
14" PPBT. N 68° E -59.3'
- ⑰ C 23-C 4
Fd: 1" G.I.P.
Ref: 10" PP. snag, scribed "C 4 C 23 867 BT", N 17° E -8.5' (N 13° E -8.5')
root hole, S 38° W -3.5' (S 38° W -3.5')
Set: AP 26" in ground in mound of stone. Buried original pipe alongside of new monument. Comp. decl. 20° East.
Ref: 10" PPBT. S 29° W -42.5'
6" PPBT. S 78° W -15.1'
- ⑱ C 22-C 1-G 4-L 3
Fd: No evidence of original pipe. Found 5/8" re-bar with cap marked "Hanley Eng", N 12° E -3.9' from corner position.
Ref: 13" White Fir BT, scribed "867", N 11° E -36.0' (N 11° E -25.3')
No evidence of southwest BT. (S 11° W -36.0')
Set: AP 26" in ground in mound of stone. Comp. decl. 20° East.
Ref: 9" DEBT. N 57° W -64.1'
8" PPBT. S 75° E -58.1'
- ⑲ NY 2-F 3-L 4-C 21
Fd: 1" G.I.P. out of position.
Ref: 24" PPBT, with weathered face, scribed "F 3-C 21 867 BT" N 14° E -34.3' (N 14° E -34.3')
18" Fir BT. stump/log, scribed "867 BT", N 36 1/2° E -66.0' (N 30° E -68.7')
Set: AP 26" in ground in mound of stone. Buried original pipe alongside of new monument. Comp. decl. 20° East.
Ref: 7" PPBT. N 46 1/2° W -12.2'
6" PPBT. N 82 1/2° E -7.0'
- ⑳ NY 3-C 24
Fd: 1" G.I.P. marked "NY 3 867 C 2"
Ref: 14" PPBT, with healed face, S 19° E -9.5' (S 19° E -9.5')
No evidence of northwest BT. (N 25° W -15.5')
Set: AP 24" in ground in mound of stone. Buried original pipe alongside of new monument. Comp. decl. 20° East.
Ref: 11" PPBT. N 30° E -39.8'

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Surveyed for: US Forest Service
Contract No. 53-04M3-1-2667N

Surveyed by: Sundet and Associates
P.O. Box 1228
Lakeview, Oregon
PhNo. 503-947-3293

Date: 1981
Drawing No. 178B Field Books 1 and 2 Sheet 2 of 2

FILED Jan. 5, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 7-43-47