


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by W. Barr, under contract no. 388, dated May 1881.

Marked basalt rock 12" x 10" x 7". Raised mound of rock.



Description of corner evidence found:

Found 12" x 10" x 7" stone with $\frac{1}{4}$ on west face. Stone is set on west edge of mound established by Drake in 1919.

Description of monument and accessories established to perpetuate the

original location of this corner: Set 2 $\frac{1}{2}$ " x 30" aluminum pipe with 3 $\frac{1}{4}$ " aluminum cap 11" in ground in mound of stone. Buried original stone alongside new monument.

Bearing Tree

14" ponderosa pine, N 01° E, 100.8 ft., scribed " $\frac{1}{4}$ S31" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

Reference Mound

3ft. x 3ft. mound of stone, S 69° W, 5.8 ft.

Compass declination 20° East

Note:

I set guard posts at corner with USFS 54-2 and 54-4 signs, placed 54-3 and 54-4 signs and painted a red band at breast height on smoothed bark on bearing tree, and placed USFS 54-3 and 54-4 signs on reference mound.

I hereby certify the above corner location was perpetuated as herein described on June 1, 1982.

T7S
 R43E R44E
 $\frac{1}{4}$
 536 | 531
 1982
 RLS 1664

Terry Butler Terry Butler, Witness
Frank Vaughn Frank Vaughn, Witness

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Carl E. Sundet
 OREGON
 JULY 14, 1978
 CARL E. SUNDET
 1664

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....

..... by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED June 29, 1982
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-43-52
7-44-32