


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by W. Barr under contract no. 388, dated May 7, 1881. Marked basalt rock 16"x14"x4" for 1/4 section corner. Raised mound of rock as per instructions.



Description of corner evidence found:

Found 16"x14"x4" stone with 1/4 scribed on north face, in a mound of stone.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2"x30" aluminum pipe with 3 1/4" aluminum cap 11" in ground in mound of stone. Buried original stone alongside of new monument. Cap marked;

Reference Mounds

4 ft. x 4 ft. mound of stone N 38° E 6.5 ft.  
4 ft. x 4 ft. mound of stone S 11° W 4.8 ft.

Compass declination 20° East

T7SR43E

1/4 S 25 / S 36

1982

RLS 1664

Note:

I set guard posts west and south of corner with FS 54-2 and 54-4 signs. I placed FS 54-3 and 54-4 signs in reference mounds.

I hereby certify the above corner location was perpetuated as herein described on July 4, 1982.

Terry Butler Terry Butler, Witness

Frank Vaughn Frank Vaughn, Witness

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Carl E. Sundet

OREGON  
JULY 14, 1978  
CARL E. SUNDET  
1664

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)