

SUNDET & ASSOCIATES

LAND SURVEYING

LAKEVIEW, OREGON 97630

PHONE 947-3293

P.O. Box 1228

August 14, 1983

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

Survey for: Wallowa-Whitman National Forest
P.O. Box 907
Baker, Oregon 97814

Location: Located in Sections 31, 36, 1 & 6, T.7 & 8S.
R.43 & 44E., Baker County, Oregon.

Purpose: Recovery of original corners, subdivision of section
and posting of lines between Forest Service and other
ownership.

Date: Survey completed in July, 1983

Procedure: Survey began with the search of original corner
evidence.

The northeast corner section 36 was remonumented
by the BLM in 1974 from original evidence.

Original evidence was found at the N $\frac{1}{4}$, W $\frac{1}{4}$ & E $\frac{1}{4}$
and at the NW and SW section corners.

At the corner to Townships 7 & 8 South, Ranges
43 & 44 East we found a 16" x 10" x 7" stone marked
with 6 notches north, south, east & west. This stone
differs greatly in size from the township corner stone
described in the original notes. We then surveyed
south, the direction from which the township corner
was originally established, and found the $\frac{1}{4}$ corner
sections 1 & 6 and the section corner 1, 6, 7 & 12.
Bearings and distances are reasonably close to orig-
inal for this line.

From notes found at the Baker County Surveyors Of-
fice dated 1914 by Ira Hoffman, we determined that
he found and used this same stone at the township cor-
ner. As no better evidence of the original corner
location could be found this stone was accepted as the
best evidence of the original corner location. The
original S $\frac{1}{4}$ corner, section 36 was not found and was
set by proportionate measurement.

FILED Aug 22, 1983

BAKER COUNTY SURVEYOR

SURVEY NO. 7-43-70