


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

BUFFALO QUARTZ CLAIM

History of original corner establishment:

Henry W. Cooke, U. S. Deputy Mineral Surveyor was appointed by the U. S. Surveyor-General's office on April 1, 1887, to execute the mineral survey of this mining claim. No mineral survey number was established for this survey under this directive. Mr. Cooke assigned his own number (M. S. No. 13) which is listed in the Bureau of Land Management records as M. S. No. 158A. For this reason the notes contain references to both those mineral survey numbers.



Hanley Engineering of Baker, Oregon, was engaged by William J. Wendt, owner of the Sanger Mine property, to survey and perpetuate the original Cooke patented claim corners by means of 2-inch diam. brass caps on 1-inch diam. galv. iron pipe posts. These monuments were set and not marked at that time. By Purchase Order No. 04M3-4-2010, the Wal-lowa-Whitman National Forest has authorized Hanley Engineering to maintain these monuments according to USFS R-6 Specifications for Cadastral Survey. They were die-stamped with the proper markings and referenced under this P.O.

Cooke set a post 4 ft long 4 ins square 24 ins in ground marked Cor No 3 B.M.C. Sur No 13 on SW face of post from which

A fir 36 ins dia bears S 89° W 50 feet dist marked Cor No 3 B.M.C. Sur No 13 B T

A tamarack 5 ins dia bears N 70° E 7 feet dist marked Cor No 3 B.M.C. Sur No 13 B T

Description of corner evidence found:

Monument described above, set in concrete, projecting about 6 ins. above the ground.

Fir bearing tree, 39 ins. dia. bears N. 89° W., 51.5 ft. dist., mkd. MC on partially healed blaze. Tree is now dead.

No evidence of the tamarack bearing tree.

Description of monument and accessories established to perpetuate the original location of this corner:

Stamped monument as shown on diagram above. Constructed stone mound surrounding monument.

New bearing trees:

- 12 ins. diam. white fir bears N. 55° E., 39.5 ft. dist., mkd BUF 3 158A BT.
- 12 ins. diam. white fir bears S. 57° E., 36.5 ft. dist., mkd. BUF 3 158A BT.

I certify the monument was correctly stamped and bearing trees established under my supervision on July 27, 1984 by Tom Fisk, Larry McBroom and Chris Mahoney.

Office of... County Surveyor... County of... Baker... Oregon... State of... I hereby certify that the within instrument was filed in this office for record on the... day of... 19....

(COUNTY OFFICIAL) by (DEPUTY)

Form R6-7100-57 (9/71)

FILED 2-12-1986 BAKER COUNTY SURVEYOR SURVEY NO. 7-43-74

REGISTERED PROFESSIONAL LAND SURVEYOR James D. Hanley OREGON SEPTEMBER 23, 1977 JAMES D. HANLEY 1206