

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.

**DIAGRAM**

T7S R43E

W 1/16

C ——— • ——— C

S3

1984

RLS 1928

Description of corner evidence found:

Corner not previously established.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 30" aluminum pipe with 3¼" aluminum cap 8" above ground marked as shown above.

Steel post 3' southwest with signs 54-9 and 54-2.

Scribed:

8" Fir "C-W 1/16 S3 BT" N73E 16.2 ft.

5" Fir "C-W 1/16 S3 BT" S29W 14.2 ft.

Nailed aluminum washers stamped "RLS 1928" above "BT" scribe on each tree.

Nailed bearing tree signs above blaze and land survey monument signs on back of both trees.

Painted blazes red and a 6" red band above blaze on each tree.

