


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Original survey executed by W.B. Barr in 1881 under Contract No. 388, dated May 7, 1881.

Set basalt rock 10"x8"x8" from which:  
14" pine bears S.48°W. 58 lks  
20" pine bears N.73°W. 57 lks



Description of corner evidence found:

NONE

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 30" long aluminum pipe with a 3 1/4" aluminum cap marked as shown above, 14" above ground, mounded with rock. Steel post with 54-9 sign set next to cap.

Scribed:

12" pine N.28°E 43.1' "1/4 S10 BT"  
13" pine S.80°E. 20.1' "1/4 S15 BT"

Attached signs 54-3 and 54-9 and nailed aluminum washers stamped "RLS 1928" by "BT" scribe on each tree. Painted blazes red & a 6" red band around both trees.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
1-20-86  
*Duane Fehringer*  
OREGON  
JULY 13, 1984  
DUANE FEHRINGER  
2118

Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

FILED 5-9-86  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-43-135