


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Original survey executed by W. B. Barr in 1881 under Contract No. 388, dated May 7, 1881.

Set basalt rock 12" x 10" x 8" from which:

- 8" Pine bears N47E 33 lks
- 10" Pine bears S41W 110 lks



Description of corner evidence found:

Found 10"x8"x6" above ground set stone with possible scribes and 30" Pine N47E 21.8 ft. with scar and 54-4 & 54-3 sign attached. Also found rotten stump S41W 72.6 ft. with possible scaring.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 30" long aluminum pipe with 3 1/4" aluminum cap 6" above ground, marked as shown above. Buried old monument alongside aluminum cap.

Set steel post with signs 54-4 attached.

Scribed:  
10" Spruce "1/4 S16 BT" N76W 65.4'

Nailed aluminum washers stamped "RLS 1928" above "BT" scribe on trees.

Painted blazes red and a 6" red band around trees.

Attached bearing tree signs above blazes and land survey monument signs to back of trees.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
1-20-86  
*Duane Fehringer*  
OREGON  
JULY 13, 1984  
DUANE FEHRINGER  
2118

Office of..... County of.....  
 State of..... I hereby certify that the within instrument was filed in this office  
 for record on the..... day of..... 19....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

FILED 5-9-86  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-43-139