

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


P-1

History of original corner establishment:

W. B. Barr conducted the survey of Township 7 South, Range 43 East, W.M., August 29 to September 8, 1881, under GLO Contract No. 388, dated May 7, 1881.

The original notes of that survey relative to this corner state the following:

Marked a basalt stone 18 ins. x 12 ins. x 8 ins. for 1/4 sec. corner. Raised mound of rock as per instructions.



Description of corner evidence found:

A basalt stone, 18 ins. x 12 ins. x 8 ins. with 1/4 marking. The stone was found in a fence rock jack in a new E-W fence line. An old down E-W fence is 8 ft. South of the new fence.

Description of monument and accessories established to perpetuate the original location of this corner:

Reestablished the corner point in the ancient East-West running fence line at the intersection of the North-South line connecting the adjacent section corners.

Set a 2 1/2 in. x 30 in. alum. pipe with a 2 1/2 in. alum cap, 30 ins. into the ground. Constructed a 36 ins. diam. stone mound around the monument. The cap is marked as shown in the corner diagram. Deposited the recovered original corner stone 1 ft. North of the monument. From the corner point:

A basalt boulder, 3 ft. x 2 ft. x 2 ft. high, bears S. 20° E., 101.0 ft dist., mkd X BO on the North face.

A basalt rock outcrop, 15 ft. x 8 ft. x 4 ft. high bears S. 20° W., 146.2 ft. dist., mkd. X BO on top.

Set a steel fence post 4 ft. North of the monument and attached a USFS 54-9 sign. Used a steel tape and staff compass set with 18 1/2° declination for measurements to X BO. Painted the X BO's red.

The ancient fence was most likely built to the 1/4 corner stone. New fence construction 8 ft. North utilized all stones in the near vicinity, including the corner stone. I believe the above method of corner relocation is most proper, considering the local evidence.

This corner was remonumented to USFS specifications on Dec. 1, 1986, witnessed by Tom Fisk and Larry McBroom.

Office of..... County Surveyor..... County of... Baker
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by

(COUNTY OFFICIAL)

(DEPUTY)
REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

★ 990-700-470

Form R6-7100-57 (9/71)

FILED 10/18/88

BAKER COUNTY SURVEYOR

SURVEY NO. 7-43-184

7-42-14