

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**


R-9

**History of original corner establishment:**

W. B. Barr conducted the survey of Township 7 South, Range 43 East, W.M., August 29 to September 8, 1881, under GLO Contract No. 338, dated May 7, 1881.

The original notes of that survey relative to this corner state the following:

Marked basalt stone 18 ins. x 16 ins. x 12 ins. for corner to secs. 20, 21, 28 and 29. Raised a mound of rock as per instructions.



**Description of corner evidence found:**

Basalt stone, 16 ins. x 12 ins. x 10 ins. lying with marked side down in a partial mound of stones. The stone has four grooves on one side and two grooves on a adjoining side.

**Description of monument and accessories established to perpetuate the**

**original location of this corner:** At the point of recovered stone:

Set a 2½ in. x 30 in. alum. pipe with a 2½ in. alum. cap 25 ins. into the ground. Constructed a 36 ins. diam. stone mound around the monument. The cap is marked as shown in the corner diagram. Buried the original stone 1 ft. North of the monument.

From the corner point:

An Ash, 7 ins. diam., bears N. 59° W., 53.9 ft. dist., mkd T7S R43E S20 BT.

An Ash, 8 ins. diam., bears S. 67° W., 52.2 ft. dist., mkd. T7S R43E S29 BT.

A 5/8 in. x 30 in. rebar bears N. 54° E., 10.0 ft., dist., with yellow plastic cap mkd. Hanley Engr PLS 1206, set flush with the ground.

A 5/8 in. x 30 in. rebar, set flush with the ground, bears S. 52° E., 12.0 ft. dist., with yellow plastic cap mkd. Hanley Engr. PLS 1206.

Set a steel fence post 4 ft. East of the monument and attached a USFS 54-9 sign. Attached USFS 54-9 and 54-3 signs to the bearing trees. Used a steel tape and staff compass to measure to bearing trees and bearing objects. Painted the face of blaze on bearing trees and a 6 in. band around the trees red.

This corner was remonumented to USFS specifications on Dec. 3, 1986, witnessed by Tom Fisk and Larry McBroom.

Office of..... County Surveyor..... County of..... Baker  
 Oregon  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*James D. Hanley*  
 OREGON  
 SEPTEMBER 23, 1977  
 JAMES D. HANLEY  
 1206

★ GPO—798-276

FILED 10/18/88  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-43-194