

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


V-3

**History of original corner establishment:**

W. B. Barr conducted the survey of Township 7 South, Range 43 East, W.M., August 29 to September 8, 1881, under GLO Contract No. 388, dated May 7, 1881.

The original notes of that survey relative to this corner state the following:

Marked a basalt rock 2 ins. x 10 ins. x 8 ins. for 1/4 sec. corner. Raised a mound of rock as per instructions.



**Description of corner evidence found:**

A basalt stone 10 ins. x 11 ins. x 14 ins. in an ancient large stone mound, marked poorly, with 1/4 visible, imbedded 5 ins. into the ground.

**Description of monument and accessories | established to perpetuate the**

**original location of this corner:** At the point of the recovered corner stone:

Set a 2 1/2 in. x 30 in. alum. pipe with a 2 1/2 in. alum. cap 26 ins. into the ground. Constructed a 36 ins. diam. stone mound around the monument. The cap is marked as shown in the corner diagram. Deposited original stone 1 ft. North of the monument. From the corner point:

A basalt outcrop 7 ft. x 4 ft. x 3 ft. bears S. 1° W., 136.6 ft. dist., mkd. X BO on the flat top West end.

A 5/8 inch x 30 inch rebar bears N. 62° E., 25.0 ft. dist., set flush with the ground, with yellow plastic cap mkd. Hanley Engr. PLS 1206.

Set a steel fence post 4 ft. North of the monument and attached a USFS 54-9 sign. Used a steel tape and staff compass set with 18 1/2° declination for measurements to X on bearing objects. Painted the X BO's red.

This corner was remonumented to USFS specifications on Dec. 1, 1986, witnessed by Tom Fisk and Larry McBroom.

Office of..... County Surveyor..... County of... Baker  
Oregon  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL)

Form R6-7100-57 (9/71)

DEPUTY  
REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

JAMES D. HANLEY  
OREGON  
SEPTEMBER 23, 1977  
JAMES D. HANLEY  
1206

★ GPO—788-276

FILED 10/18/88  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-43-198