


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-5

**History of original corner establishment:**

W. B. Barr conducted the survey of Township 7 South, Range 43 East, W.M., August 29 to September 8, 1881, under GLO Contract No. 388, dated May 7, 1881.



The original notes of that survey relative to this corner state the following:

Marked basalt stone 18 ins. x 8 ins. x 10 ins. for 1/4 section corner. Raised mound of rock as per instructions.

**Description of corner evidence found:**

Found 10 in. x 10 in. x 24 in. basalt stone mkd 1/4 on one face, layed over in a mound of stones.

**Description of monument and accessories | established to perpetuate the original location of this corner:**

At the point of the recovered stone:

Set a 2½ in. x 30 in. alum. pipe with a 2½ in. alum. cap 24 ins. into the ground. Constructed a 36 ins. diam. stone mound around the monument. The cap is marked as shown in the corner diagram. Deposited corner stone 1 ft. North of corner point. From the corner point:

A 5/8 in. x 30 in. rebar, set flush with ground, bears S. 44° E., 20.0 ft. dist., with yellow plastic cap mkd. Hanley Engr. PLS 1206.


A 5 ft. x 4 ft. x 4 ft. rock outcrop bears S. 30° W., 143.0 ft. to X BO chiseled on top of rock.

Set a steel fence post 4 ft. North of the monument and attached a USFS 54-9 sign. Used a steel tape and staff compass set with 18½° declination for measurements to X on bearing objects. Painted the X BO red.

This corner was remonumented to USFS specifications on Dec. 2, 1986, witnessed by Tom Fisk and Larry McBroom.

Office of..... County Surveyor..... County of... Baker.....  
Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL)

Form R6-7100-57 (9/71)



James D. Hanley  
OREGON  
SEPTEMBER 23, 1977  
JAMES D. HANLEY  
206

★ OPC-788  
FILED 10/18  
BAKER COUNTY  
SURVEY NO. 7