

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1887 by Henry W. Cook as a deputy Mineral Surveyor. Set was a post 4.5 ft. long 4 in. sq. marked Cor No 3 BMC Sur. No 11 from which:

A pine 20 in. dia. bears S 70 E, 4.5 ft, marked Cor. No. 3 BMC Sur. No 11 Bt.

A fir 18 in. dia. bears N 31 W 20 ft, marked Cor. No 3 BMC Sur. No 11 BT.

DIAGRAM

BMC No 3
MS 11

3

1973
645

Description of corner evidence found:

At corner location I found 2 badly rotted stumps with BT scribed on them. Both fit the dist. and bearings of the original notes, although the 18 in. fir was actually a pine.

Description of monument and accessories I established to perpetuate the original location of this corner

As the bearings and distances agreed to the original notes, I set a 36 in. galv. iron pipe 2 in. in dia. with a 2 in. brass cap marked as shown in the diagram.

New bearing trees:

A red fir 10 in. in dia. bears N 15 W, 32.8 ft. scribed BMC No 3 BT.

A pine 32 in. in dia. bears S 70 E, 17.3 ft. scribed BMC No 3 BT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton
10-10-73

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 14 day of December, 1973, at 9:05 o'clock A.m. (signed)
..... by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)

SURVEY NO. 7-44-4