

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established in 1887 by Henry W. Cook as a deputy Mineral Surveyor.

Set was a post 4.5 ft. long 4 in. sq. marked Cor No 4 BMC Sur 11 from which:

A fir 14 in. dia. bears S 10 E, 12 in. marked Cor No 4 BMC Sur. 11 BT.

A pine 12 in. dia. bears N 88 W, 6.5 feet marked Cor No 4 BMC Sur 11 BT.

DIAGRAM

BMC No 4
MS 11

1973
645

Description of corner evidence found:

At corner location I found post rotted to a length of 18 in. with markings Cor No 4 BMC Sur 11, also I found a pine 24 in. dia, with scribing Cor No 4 BMC Sur 11 BT and a fir 22 in. dia. with scribing on bark Cor No 4 BMC Sur 11 BT.

Description of monument and accessories I established to perpetuate the original location of this corner

As the evidence agrees to the original survey notes, I set a 36 in. galv. iron pipe, 2 in. in dia. with a 2 in. brass cap, marked as shown in the diagram. I placed the old post along side the pipe and a mound of stone.

New bearing tree:

A red fir 6 in. dia. bears N 43 E, 20.0 ft. scribed BMC No 4 BT.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James H. Hambleton
10-10-73

OREGON
JULY 10, 1964
JAMES H. HAMBLETON
645

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 14 day of December, 1973, at 7:15 o'clock A.m., (signed)
by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)

SURVEY NO. 7-44-5