

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by W. B. Barr under G L O contract No. 388 dated May 7, 1881.

Surveyor's General records state:

Marked basalt rock 15x10x6 for corner to secs 1, 6, 7, 12 from which:

- Tamarack 15 ins diam bears N 76° W, 23 lks dist
- Pine 50 ins diam bears S 32° W, 80 lks dist
- Pine 36 ins diam bears S 14° E, 33 lks dist
- Tamarack 20 ins diam bears N 57° E, 68 lks dist

Description of corner evidence found:

None

Corner remonumented by single proportionate measure between the north-east corner of Section 6 (township corner) and the west quarter-section corner of Section 7.


Description of monument and accessories established to perpetuate the original location of this corner

Set a 2½ inch brass cap on a 2 inch iron pipe, 31 inches long, 20 inches in the ground with a surrounding dirt and rock mound, from which:

New bearing trees:

- A tamarack, 8 ins diam bears N 50° E, 11.6 ft dist marked T 7 S R 44 E S 6 BT
- A fir, 10 ins diam bears S 79° E, 10.2 ft dist marked T 7 S R 44 E S 7 BT
- A fir, 8 ins diam bears S 04° W, 15.7 ft dist marked T 7 S R 43 E S 12 BT
- A tamarack, 10 ins diam bears N 44° W, 32.6 ft dist marked T 7 S R 43 E S 1 BT

Brass cap marked thus:



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

I hereby certify that the above corner monument was properly re-established on July 25, 1978 witnessed by B. Hanley and R. Spivey.

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____

(COUNTY OFFICIAL) by _____ (DEPUTY)

FILED Aug 11, 1978

BAKER COUNTY SURVEYOR
SURVEY NO. 7-44-8
7-43-2