


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by W. B. Barr under G L O contract No. 503 dated May 23, 1884.

Surveyor's General records state:

Set a limestone 14 x 7 x 7 ins, 10 ins in the ground for 1/4 sec cor marked 1/4 on the W side from which:



A fir 6 ins diam bears N 23° E, 51 lks dist marked 1/4 S BT  
 A fir 5 ins diam bears S 17° W, 8 lks dist marked 1/4 S BT


Description of corner evidence found:

None

This corner is remonumented at the position explained in "NARRATIVE, SURVEY FOR COLLINS PINE CO." filed Oct. 4, 1978, under Survey No. 7-44-11.

Description of monument and accessories established to perpetuate the original location of this corner

At corner location as determined by survey (see survey No. 7-44-11) set a 2 1/2 inch brass cap on a 1 inch iron pipe, 31 inches long, 26 inches in the ground marked thus:



New bearing trees:

A fir 10 ins diam bears N 63° E, 23.6 ft dist marked 1/4 S 5 BT  
 A pine 8 ins diam bears N 38° W, 15.0 ft dist marked 1/4 S 6 BT

Each BT has a sign 54-5 attached below a band of red paint and has a sign 54-4 attached on opposite side of tree.

I hereby certify the above corner monument was re-established as herein described and witnessed by Bill Hanley (instrumentman) and Rob McKim (chainman) on August 18, 1978.

Office of County Surveyor ..... County of Baker  
Oregon ..... I hereby certify that the within instrument was filed in this office  
 for record on the ..... day of .....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*James D. Hanley*

**OREGON**  
 SEPTEMBER 23, 1977  
**JAMES D. HANLEY**  
 1206

FILED Dec. 8, 1978  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-44-12