


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by W. Barr under contract #503, dated May 23, 1884.

Set stone 11"x10"x6" from which;
a pine 18" in diameter bears N 38° E 59 links distance
a pine 8" in diameter bears S 09° E 23 links distance

Re-monumented by BLM in 1974. Set a 2 1/2"x28" iron post 22" in ground; from which;
a fir 6" in diameter bears N 29 1/2° W 24 links distance, marked "1/4 S 28 BT"
Brass cap marked; T 7 S R 44 E



1/4 S 28
33
1974

Description of corner evidence found:

Found BLM brass cap, 1974.

Found;

- 28" ponderosa pine snag N 38° E 59 links
23" ponderosa pine S 09° E 23 links chopped open face
7" fir N 29 1/2° W 24 links, healed face

Description of monument and accessories I established to perpetuate the original location of this corner:

New bearing tree
a fir 11" in diameter bears S 50° E 22.5 feet distance, scribed "1/4 S 33" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.
Compass declination 20° East

Note

I set a steel fence post with USFS Attention sign at corner, placed USFS bearing tree signs on all bearing trees, and painted red band on smooth bark at breast height on all bearing trees.

I hereby certify the above corner was perpetuated as herein described on September 15, 1981.

Terry Butler Terry Eutler, Witness

REGISTERED PROFESSIONAL LAND SURVEYOR

Carl E. Sundet
OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
(COUNTY OFFICIAL) (DEPUTY)