

CERTIFIED RECORD OF LAND CORNER MONUMENTATION



History of original corner establishment:

Corner originally established by W. Barr under contract #503, dated May 23, 1884.

Set a basalt rock 16"x14"x8" from which;  
 a pine 14" diameter bears N 05° E 190 lks  
 a pine 20" diameter bears S 17° E 54 lks  
 a pine 18" diameter bears S 23° W 45 lks  
 a pine 24" diameter bears N 75° W 75 lks

Re-monumented by BLM in 1974. Set a 2½"x28" iron post 10" in ground to bedrock in large mound of stone, from which;

a fir, 15" in diameter bears S 83° W 94 links distance, marked "T7SR/44ES19" "BT" Brass cap marked;



Description of corner evidence found:

Found BLM Brass Cap, 1974.

Found:

21" Ponderosa Pine N 64° E 190 lks  
 29" Fir S 17° E 54 lks  
 16" Fir S 83° W 94 lks  
 Root hole S 23° W 45 lks  
 Root hole N 75° W 75 lks

Description of monument and accessories established to perpetuate the original location of this corner:

New Bearing tree  
 4" Ponderosa Pine N 33½° W 15½ ft. scribed " X " in upper blaze and " BT " and brass tag stamped RLS 1664 in lower blaze.

Compass declination 20¼° East

Note:

I set steel fence post at corner with USFS Attention sign, placed USFS bearing tree signs on all bearing trees, and painted red band on smooth bark band at breast height on all bearing trees.

I hereby certify the above corner was perpetuated as herein described in August 1981.

*Terry Butler* Terry Butler, Witness  
*Frank Vaughn* Frank Vaughn, Witness

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Carl E. Sundet*

OREGON  
 JULY 14, 1978  
 CARL E. SUNDET  
 1664

Office of..... County of.....  
 State of..... I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED OCT 23, 1981  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-44-14