


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by W.B. Barr under contract #503, dated May 23, 1884.
Set post 4 ft. long and 4 in. diameter, 24 in. in ground from which;
a pine 30 in. diameter bears S 30° E 37 links
a pine 30 in. diameter bears S 30° W 40 links



Description of corner evidence found:

No evidence of stake.

Found:

24" ponderosa pine stump - rotten - S34°W - 40 lks lower face scribing burnt off
31" ponderosa pine - alive with partly burnt face S26°E - 37 lks - scribed "1/4 S" "BT"

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" x 30" aluminum pipe with 3 1/4" aluminum cap 24" in ground in mound of stone, marked:



Bearing trees:

12" ponderosa pine - N34°W - 26.0 ft. - scribed "1/4 S31" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze
6" ponderosa pine N81°E - 19.6 ft. - scribed "1/4 S32" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze

Compass declination 20°30' East

Note:

I set steel fence post at corner with USFS Attention sign, placed USFS bearing tree signs on all bearing trees and painted red band on smoothed bark at breast height on all bearing trees.

I hereby certify the above corner location was perpetuated as herein described in August 1981.

Terry Butler Terry Butler, Witness
Frank Vaughn Frank Vaughn, Witness

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Oct 22, 1981
BAKER COUNTY SURVEYOR
SURVEY NO. 7-44-18

☆ GPO-798-276