


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Walden under contract #198,
dated July 15, 1873.
Set basalt rock 16" x 8" x 6", 8" in ground.




Description of corner evidence found:

Found:
13" x 9" x 4" stone with $\frac{1}{4}$ on north face.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 $\frac{1}{2}$ " x 30" aluminum pipe with 3 $\frac{1}{4}$ " aluminum cap, 26" in ground in mound of stone, marked:
Buried original stone alongside new monument.



Bearing trees:

5" ponderosa pine - N68 $\frac{1}{2}$ ° E - 89.2 ft. - scribed " $\frac{1}{4}$ S31" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.
10" ponderosa pine - S16° W - 182.0 ft. - scribed " $\frac{1}{4}$ S6" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.
Compass declination° 20 East

Note:

I set a steel fence post at corner, with USFS Attention sign, placed USFS 54-3 signs on all bearing trees and painted red band on smoothed bark at breast height on all bearing trees.

I hereby certify the above corner location was perpetuated as herein described in November 1981.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Terry Butler Terry Butler, Witness

Carl E. Sundet

Frank Vaughn Frank Vaughn, Witness

OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by

(COUNTY OFFICIAL)

(DEPUTY)