


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by C. M. Foster in December 1882 under instructions dated October 23, 1882.

Set a 4" x 4" squared post in ground supported by a mound of rocks, marked E.M.W. No. 1-126.



Description of corner evidence found:

Found mound of stone with a 4" x 4" squared post. This post not original.

Description of monument and accessories | established to perpetuate the

original location of this corner: Set a 2 1/2" x 30" aluminum pipe with a 3/4" aluminum cap 24" in ground in mound of stone. Buried broken clear glass alongside pipe. Cap marked;

Bearing Trees

7" ponderosa pine, N 31° E, 34.3 ft., scribed "EMW1 MS 126" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.


6" ponderosa pine, S 44° W, 33.9 ft., scribed "EMW1 MS 126" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

Compass declination 20° East.

Note:

I set steel fence posts at corner with USFS 54-4 and 54-2 signs and place USFS 54-4 and 54-8 signs and painted a red band on smoothed bark at breast height on bearing trees.

I hereby certify the above corner location was perpetuated as herein described on May 13, 1982.



Terry Butler Terry Butler, Witness
Frank Vaughn Frank Vaughn, Witness

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
 OREGON
 JULY 14, 1978
 CARL E. SUNDET
 1664

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by.....
 (COUNTY OFFICIAL) (DEPUTY)