

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


Corner established by W. B. Barr under GLO contract no. 503, dated May 23, 1884.

Surveyor General records state:

Set limestone 20x12x6 ins 15 ins in ground for 1/4 sec cor marked 1/4 on the N. side from which;

A tamarack 6 ins diam bears S 17° W, 21 lks dist marked 1/4 S BT

A tamarack 4 ins diam bears N 27° E, 14 lks dist marked 1/4 S BT



Description of corner evidence found:

This corner was searched for during the course of survey for Collins Pine Co. in 1977 and 1978, and again this date in location determined from survey between the adjacent section corners East and West. No trace was found of original stone or bearing trees.

Amended by Survey No. 7-44-36

Description of monument and accessories established to perpetuate the original location of this corner:

At the position determined by single proportionate measurement along the South line of Section 6, set a 2½ inch brass cap on a 2 inch iron pipe, 31 inches long and projecting 6 inches out of the ground with a surrounding rock mound.

Brass cap marked thus: T 7 S R 44 E

$\frac{1}{4}$ $\frac{S 6}{S 7}$

1982

ORLS 1639

New bearing trees:

A fir 9 inches diam bears S 69° E, 7.2 feet dist marked 1/4 S 7 BT

A fir 9 inches diam bears N 23° E, 24.7 feet dist marked 1/4 S 6 BT

I hereby certify that the above described corner monument was properly reestablished by me on August 24, 1982, and witnessed by Brad Gordon, Tom Fisk and Jim DeMastus.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-51 (9/71)

FILED Aug. 24, 1982

☆ GPO—798-276

BAKER COUNTY SURVEYOR

SURVEY NO. 7-44-33