



SURVEY NARRATIVE

This survey was performed at the request of the U. S. Forest Service for the purpose of monumenting the South quarter-section corner of Section 6, T 7 S, R 44 E, W.M. The South line of the said Section 6 was previously surveyed by me in 1977 and 1978 and filed in the Baker County Surveyor records under Survey No. 7-44-11. During the course of that previous survey, the Southwest corner of Section 6 was monumented as described in Survey No. 7-44-8. On August 24, 1982, I resurveyed the said South line of Section 6 and found the length of that line to be 42.84 feet shorter than reported on said Survey No. 7-44-11. Although the previous survey incorporated closed loop traverses, I relied on the latter measurements for the replacement of the said South quarter-section corner. Also, I planned to check my work for errors, and especially for a scribners error in recordation of the length of the said South line. No errors were to be found upon first reviewing this situation until Barry B. Barbour, land surveyor, reported an unknown discrepancy regards the Southwest corner of the said Section 6. Further checking revealed that the original reestablishment of the said Southwest corner was in error due to a field miscalculation at the time of corner reestablishment.

The Southwest corner and the South quarter-section corner of Section 6 were properly reestablished in their true proportioned positions. The old bearing trees for the Southwest corner were defaced and new bearing trees scribed in their place. The bearing trees to the South quarter-section corner were not defaced and the tags changed to reflect the relocated position of the corner.

Meridian by Survey No. 7-44-11.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

NOTE: For monumentation records see Survey Nos. 7-44-35 & 7-44-36.

FILED Oct. 5, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 7-44-34

MAP OF SURVEY
THE SOUTH LINE SECTION 6, T 7 S, R 44 E, W.M.
Surveyed Aug. 24, & Oct. 4, 1982 1"=500'
For U. S. Forest Service