

# SUNDET & ASSOCIATES

LAND SURVEYING

LAKEVIEW, OREGON 97630  
PHONE 947-3293  
P.O. Box 1228

September 22, 1982

## SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

Survey for: Wallowa-Whitman National Forest  
P.O. Box 907  
Baker, Oregon 97814

Location: Section 19 and a portion of section 30,  
T.7S. R.44E. W.M., Baker County, Oregon

Purpose: To monument and define boundaries of Federal  
ownership.

Date: Survey commenced August 1981

Procedure: Survey began with the search of original corners. BLM notes show all original corners in section 19 were remonumented and perpetuated in 1974 excepting the east  $\frac{1}{4}$  corner. Field examination of these corners found them to be as per BLM notes with the exception of the NW section corner where the brass cap was missing. A new monument was set from existing bearing trees. At the east  $\frac{1}{4}$  corner we found the original stone, the scribed remains of one bearing tree, and the rotted remains of the other bearing tree. This corner was remonumented and perpetuated at this time.

A closed traverse was then run around the section tying in all corners except the NE section corner, which was not needed for subdivision work within the section.

The section subdivision was performed in accordance with the BLM Manual of Instructions, 1973 taking into account the supplemental plat of section 19 dated February, 1946 creating lot 7. The metes and bounds lines were run in accordance with the title report prepared by the Elkhorn Title Company, Baker Oregon, dated November 18, 1981.

Property lines between Forest Service and other ownership were marked with steel or wood posts and Forest Service property boundary signs.

Instruments used were a Mac I-H Electronic Distance Measuring Device, Jena one-second theolodite, 4" K&E Staff Compass and 100' steel tape.

Bearings based on solar observation.

FILED Oct 19 1982  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-44-40