


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None



Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2¼" x 30" aluminum pipe with 3¼" aluminum cap 26" in ground in small mound of stone, marked;



Bearing trees:

8" white-fir - N07°W - 19.3 ft. scribed "C¼ S19" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze  
9" white fir - N64°E - 33.8 ft. scribed "C¼ S19" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze

Compass declination 20° East

Note:

I set steel fence post at corner location with USFS 54-9 sign, placed USFS bearing tree signs on all bearing trees and painted red band at breast height on smoothed bark on all bearing trees.

I hereby certify the above corner location was perpetuated as herein described in August 1982.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Carl E. Sundet*

OREGON  
JULY 14, 1978  
CARL E. SUNDET  
1664

Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

FILED Dec 20 1982  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-44-45