


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None



Description of corner evidence found:

None

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2½" x 30" aluminum pipe with ¾" aluminum cap 26" in ground in mound of stone, marked:



Bearing trees:

- 11" ponderosa pine - N49.5°W - 71.1 ft. scribed "NW1/16 S19" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze
- 13" ponderosa pine - S83°W - 62.3 ft. scribed "NW1/16 S19" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze

Compass declination 20° East

Note:

I set steel fence post at corner location with USFS 54-9 sign, placed USFS bearing tree signs on all bearing trees and painted red band at breast height on smoothed bark on all bearing trees.

I hereby certify the above corner was perpetuated as herein described in August 1982

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Carl E. Sundet*  
OREGON  
JULY 14, 1978  
CARL E. SUNDET  
1664

Office of..... County of.....  
 State of..... I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED Dec 20 1982  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-44-54