


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Walden under contract #198 dated July 1873

Set granite rock 14" x 10" x 8" 8" in ground



Description of corner evidence found:

Found 14"x8"x6" stone in mound of stone with ¼ on north face

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2½" x 30" aluminum pipe with 3¼" aluminum cap 24" in ground in mound of stone, marked:



Bearing trees:

- 5" ponderosa pine - N68.5°E - 13.5 ft. scribed "¼ S36" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze
- 11" ponderosa pine - S22°E - 27.4 ft. scribed "¼ S1" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze

Compass declination 20.75° East

Note:

I set steel fence post 5' east of corner with USFS attention sign, placed USFS bearing tree signs on all bearing trees and painted red band at breast height on smoothed bark on all bearing trees

I hereby certify the above corner was perpetuated as herein described in November 1982

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by (DEPUTY)
 (COUNTY OFFICIAL)

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Carl E. Sundet

OREGON
 JULY 14, 1978
 CARL E. SUNDET
 1664