


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Walden under contract #198 dated July 1873.

Set granite stone 12" x 10" x 6" 6" in ground.



Description of corner evidence found:

Found 12" x 10" x 6" scribed stone.

Unrecorded bearing trees:

- 30" douglas fir - N66½°E - 29.4 ft. scribed R44E S34
- 30" ponderosa pine - dead, down and moved scribed T8S R44E S4 BT
- Rotten stump - S89°E - 53.6 ft. scribed R44E S3 BT

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2½" x 30" aluminum pipe with ¾" aluminum cap 26" in ground, Marked:  
Buried original stone alongside pipe.  
No stones available for mound.



Bearing trees:

- 15" ponderosa pine - N18°E - 83.5 ft. scribed "T7SR44E S34" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze
  - 7" ponderosa pine - S06½°E - 71.4 ft. scribed "T8SR44E S3" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze
  - 13" ponderosa pine - S36°W - 66.4 ft. scribed T8SR44E S4" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze
  - 7" douglas fir - N61°W - 77.7 ft. scribed T7SR44E S33" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze
- Compass declination 19 3/4° East

Note:

I set steel fence post 6' east of corner with USFS 54-4 sign, placed USFS bearing tree and attention signs on all bearing trees and painted red band at breast height on smoothed bark on all bearing trees.

I hereby certify the above corner was perpetuated as herein described in May 1983

Witness: Ron Horton

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 by.....  
 (COUNTY OFFICIAL) (DEPUTY)

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Carl E. Sundet*

OREGON  
JULY 14, 1978  
CARL E. SUNDET  
1664