


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Walden under contract #198 dated July 1873.

Set basalt rock 14" x 8" x 6" 8" in ground.




Description of corner evidence found:

No evidence of original stone.  
Set by single proportionate measurement.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2½" x 30" aluminum pipe with ¾" aluminum cap 22" in ground in mound of stone, marked:



Bearing trees:

- 13" ponderosa pine - N44½°W - 51.0 ft. scribed "T7SR44E S35" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze
- 15" ponderosa pine - N43½°E - 64.1 ft. scribed "T7SR44E S36" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze
- 10" ponderosa pine - S34°E - 85.1 ft. scribed "T8SR44E S1" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze
- 9" ponderosa pine - S70½°W - 71.0 ft. scribed "T8SR44E S2" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze

Compass declination 19 ¾° East

Note:

I set steel fence post 6' east of corner with USFS 54-4 sign, placed USFS bearing tree and attention signs on all bearing trees and painted red band on smoothed bark at breast height on all bearing trees.

I hereby certify the above corner was perpetuated as herein described in June 1983.

Witness: Ron Horton

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Carl E. Sundet*

OREGON  
JULY 14, 1978  
CARL E. SUNDET  
1564

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

FILED July 25 1983  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-44-69  
8-44-50