

NARRATIVE: T7S, R44E, W. M. (cont.)

Eagle Creek is the most prominent feature in this township. The only place that Barr seems to have this feature correctly located, is on the line between sections 7 and 8. It appears that Barr started this survey in the southwest corner and went north and east. Eagle Creek was avoided as much as possible. A great number of corners in the middle of the township have never been found. At least 30 some trees were searched for and not found. The topographic calls can define about where the corner should be, but no not fit tightly. This resulted in having to put in several corners by double and single proportionate measurements. Several corners fall in or near Eagle Creek and some on the opposite side of the creek, from the record notes.

The survey was performed from May, 1982 to June, 1985. A Wild T-2, with 3 Wild tribrachs and a Mac II-H EDM were used to run closed loop traverses. The bearings are based on solar observations. The property boundarys were marked with 6' steel fence posts and U. S. F. S. 54-2s.

August 21, 1985.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051