


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number A-15

History of original corner establishment:

Corner was originally established under G. L. O. contract number 503, by W. B. Barr, on June 2, 1884. Surveyor General's notes state: "Set granite rock 10 X 10 X 8 ins. 7 inches in fround for 1/4 sec. cor. marked 1/4 on the N. side. From which a fir 14 ins. diam. bears S83°E, 114 lks. dist. marked 1/4S BT. A fir 7 ins. diam. bears N10°E, 54 lks. dist. marked 1/4S BT."



In 1974 the BLM remonumented this corner. Official notes state: "At corner point, Set an iron post, 28 ins. long, 2 1/2 ins. diam., 18 ins. in the ground to bedrock, and in a mound of stone, 3 ft. base, to top, with brass cap marked: From which new bearing trees. A white fir, 7 ins. diam., bears S59°W, 75 lks. dist., mkd. 1/4 S3 BT. A white fir, 15 ins. diam., bears N80°W, 108 lks. dist., mkd. 1/4 S34 BT."

Description of corner evidence found:

Found no trace of record BLM brass cap corner. Found an 8" Fir with grown over blaze. Measured N59°E, 49.5 ft. From here a 16" Fir bears N77°W, 70.0 ft. with partially grown over blazes. These are the 1974 BLM bearing trees. A 24" Fir with grown over blaze bears N18°E, 34.0 ft. A 36" stump bears S89°E, 46.5 ft. These are the original G. L. O. bearing trees.

Description of monument and accessories established to perpetuate the original location of this corner:

At measured point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 22" in the ground and mound of stone around to cap. Painted blazes red and 6" red band around. Bearing trees have 54-3s and 54-4s. Placed 54-4 on a steel fence post 5' east of the corner.

R44E  
S34 T6S  
1/4  
S3 T7S  
OR PLS 1051  
1982

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Larry D. Shirley  
Daniel T. Rowland

July 13, 1982.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Barry B. Barbour*

OREGON  
OCT. 17, 1975  
BARRY B. BARBOUR  
1051

Office of.....County Surveyor..... County of.....Baker.....  
State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 1985  
..... by .....

(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

FILED 11-7-85  
BAKER COUNTY SURVEYOR  
SURVEY NO. 7-44-79