


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number G-3

History of original corner establishment:

Not Set.



Description of corner evidence found:

None Found.

Description of monument and accessories I established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked:  
Set pipe 22" in the ground and mound of stone around to cap.

T7S R44E  
 C1/4 + S7  
 OR PLS 1051  
 1982

From which by magnetic declination of N20°E:  
A 9" Fir bears N83°E, 34.5 ft. scribed C1/4 S7 BT. An 8" Pine bears S11°E, 50.7 ft. scribed C1/4 S7 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on the bearing trees. Placed 54-2 and 54-9 on a steel fence post 5' south and placed 54-2 on a steel fence post 5' west of the corner.

I hereby certify that the above corner monument was established as herein described.

Witnesses: Larry D. Shirley  
 Michael L. Cain

October 15, 1982.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Barry B. Barbour*

OREGON  
 OCT. 17, 1975  
 BARRY B. BARBOUR  
 1051

Office of.....County Surveyor..... County of.....Baker.....  
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 1985.

(COUNTY OFFICIAL)

by

(DEPUTY)

FILED 11-7-85  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 7-44-86