


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File Number L-7

History of original corner establishment:

Not set.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2" X 30" aluminum pipe and cap marked: T7S R44E
 Set pipe 22" in the ground and mound of stone around to cap. OR PLS 1051
 From which by magnetic declination of N20°E: 1985
 A 20" Fir, bears N33°E, 57.3 ft. scribed C1/4 S17 BT. A 15"
 Fir bears S54°E, 32.7 ft. scribed C1/4 S17 BT. Painted blazes red and 6"
 red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051
 on the bearing trees. Placed 54-9 on a steel fence post 5' south of the
 corner.

I hereby certify that the above corner monument was established as herein described.

Witnesses: Van K. Barbour
Daniel J. McMillan

August 24, 1985.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour
 OREGON
 OCT. 17, 1975
 BARRY B. BARBOUR
 1051

Office of..... County Surveyor's..... County of..... Baker.....
 State of..... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... 19.85
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED 11-7-85
 BAKER COUNTY SURVEYOR
 SURVEY NO. 7-44-101